GODIVA PROPERTIES PRIVATE LIMITED

A-102,ICC Trade Tower, Senapati Bapat Road, Shivaji Nagar,411016,Maharashtra,IN
Pan No. AAACH5157J , GSTIN No.: 27AAACH5157J1ZG

Work Order

Purchase Order No: 2220005654	**PO Date:** 06.10.2025
Delivery Date: 06.10.2025	**Indent Number:**
Project Name: / Kohinoor World Towers-Mundhwa / Techanical Overheads	**Indent Date:**
Start Date:	**End Date:**
Supplier Name & Address	**Delivery Address**
To, VERTSCEND AUTOMATION PVT. LTD ,BEHIND MAHAVEER ELECTRONICS,PUNE,Maharashtra,India,411037 GSTIN No: 27AAFCV9527P1ZF PAN No: AAFCV9527P **Contact Person:** **Mobile No:** 9767193900 **E-Mail:** varunjadhav@vertscend.com	From, Kohinoor World Towers-Mundhwa Mundhwa,Pune,Maharashtra,India,410038 **Contact Person :** **Mobile No :**

Preface: WO For Time Laps CCTV Camera At KWT Mundhwa

With reference to our communication we are pleased to place you an order whose details are as follows

Sr No.	SAC Code	BOQ Details	Qty	UOM	Rate	TAX %	Basic Amt
1		Time Laps CCTV Camera	1	AU	1,75,000.00	0.00	1,75,000.00
1 .1		Supply,Installation,Integration,Testing And commissioning of the complete CCTV system comprising DS-7608NXI/I2/S08 Channel Time-Lapse NVR with 2 SATA (80 Mbps bandwidth), SS-NE30XSP- M5 6.0 MP Outdoor 30X IP Speed Dome Cameras withPOE power supply, face and vehicle detection, 8 TB HDD, 4-port PoE switch with 2 Giga uplink, 5x5 PVC boxes for camera connections, 4U wall-mount rack with tray, PDU,accessories, 19" HDMI & VGA monitor, supply and laying of CAT6 cable and6-core fiber unarmoured cable with all necessary accessories such as PVCconduit, sockets, saddles, etc. (approx. per meter charges), fiber mediaconverter, pigtail, splicing, 2-way big enclosures, and outdoor network box The work shall be completed in all respects as per manufacturer's specifications and instructions of the Site In-Charge.	1	EA	1,75,000.00	18.00	1,75,000.00
						Sub Total Amount:	1,75,000.00
						CGST:	15,750.00
						SGST:	15,750.00
						Net Total Amount	2,06,500.00

Amount in Words: Two Lakh Six Thousand Five Hundred Rupees

Payment Terms:

Terms and Conditions

Order Acceptance

For, Godiva Properties Private Limited

PO Created By	Checked By	Approved By

GODIVA PROPERTIES PRIVATE LIMITED

KOHINOOR

A-102,ICC Trade Tower, Senapati Bapat Road, Shivaji Nagar,411016,Maharashtra,IN
Pan No. AAACH5157J , GSTIN No.: 27AAACH5157J1ZG

Work Order

Purchase Order No: 2220005654	**PO Date:** 06.10.2025
Delivery Date: 06.10.2025	**Indent Number:**
Project Name: / Kohinoor World Towers-Mundhwa / Tower B	**Indent Date:**
Start Date:	**End Date:**
Supplier Name & Address	**Delivery Address**
To, VERTSCEND AUTOMATION PVT. LTD ,BEHIND MAHAVEER ELECTRONICS,PUNE,Maharashtra,India,411037 GSTIN No: 27AAFCV9527P1ZF PAN No: AAFCV9527P **Contact Person:** **Mobile No:** 9767193900 **E-Mail:** varunjadhav@vertscend.com	From, Kohinoor World Towers-Mundhwa Mundhwa,Pune,Maharashtra,India,410038 **Contact Person :** **Mobile No :**

Preface: WO For Time Laps CCTV Camera At KWT Mundhwa

With reference to our communication we are pleased to place you an order whose details are as follows

Sr No.	SAC Code	BOQ Details	Qty	UOM	Rate	TAX %	Basic Amt
1		Time Laps CCTV Camera	1	AU	1,75,000.00	0.00	1,75,000.00
1 .1		Supply,Installation,Integration,Testing And commissioning of the complete CCTV system comprising DS-7608NXI/I2/S08 Channel Time-Lapse NVR with 2 SATA (80 Mbps bandwidth), SS-NE30XSP- M5 6.0 MP Outdoor 30X IP Speed Dome Cameras withPOE power supply, face and vehicle detection, 8 TB HDD, 4-port PoE switch with 2 Giga uplink, 5x5 PVC boxes for camera connections, 4U wall-mount rack with tray, PDU,accessories, 19" HDMI & VGA monitor, supply and laying of CAT6 cable and6-core fiber unarmoured cable with all necessary accessories such as PVCconduit, sockets, saddles, etc. (approx. per meter charges), fiber mediaconverter, pigtail, splicing, 2-way big enclosures, and outdoor network box The work shall be completed in all respects as per manufacturer's specifications and instructions of the Site In-Charge.	1	EA	1,75,000.00	18.00	1,75,000.00
						Sub Total Amount:	1,75,000.00
						CGST:	15,750.00
						SGST:	15,750.00
						Net Total Amount	2,06,500.00

Amount in Words: Two Lakh Six Thousand Five Hundred Rupees

Payment Terms:

Terms and Conditions

Order Acceptance

For, Godiva Properties Private Limited

06/10/25

06 Oct 2025

PO Created By	Checked By	Approved By

DRAFT

Contract Scope:

ARTICLE: 1

1.1In general, the scope of the Contractor shall include the supply, delivery, installation, integration, testing, and commissioning of the complete CCTV Surveillance System with all required materials and accessories. The system shall consist of, but not be limited to, DS-7608NXI/I2/S Time-lapse NVR (08 Channel with 2 SATA and 80 Mbps bandwidth), SS-NE30XSP-M5 6.0 MP Outdoor 30X IP Speed Dome Camera with Progressive Scan CMOS Sensor, POE Power Supply, Face Detection and Vehicle Detection, 8 TB HDD, 4-port PoE switch with 2 Giga uplink ports, 5x5 PVC box for camera connections, 4U wall mount rack with tray and PDU, 19" HDMI & VGA monitor, CAT6 cabling with accessories, 6-core fiber unarmoured cable with accessories, fiber media converter, 2-way big enclosure, pigtails, splicing, and outdoor network boxes.

1.2The Contractor shall be fully responsible for the supply and installation of all equipment and accessories as per the approved sp

ecifications and designated locations. This shall include mounting, cable laying, power connectivity, and complete integration with the existing AV/IT/Security systems.

1.3The Contractor shall carry out complete testing and commissioning of the system. This shall include verification of recording, playback, storage, face detection, and vehicle detection functions; checking of all input/output ports, switches, and network connections; calibration of cameras including focus, zoom, and resolution; and demonstrating full integration with existing networks. A functional demonstration shall be provided to the Client's representative, and all testing shall be conducted strictly as per OEM guidelines and approved standard operating procedures. Written sign-off from the Engineer-in-Charge or designated authority shall be mandatory for final acceptance of commissioning.

1.4The Contractor shall provide a comprehensive onsite warranty of Two (2) years from the date of successful installation and commissioning. This warranty shall cover all equipment including cameras, NVR, HDD, switches, racks, monitors, ports, cables, and accessories, against manufacturing defects, hardware failures, and software malfunctions under normal usage. The Contractor shall ensure prompt service support, including repair or replacement of defective parts at no additional cost. Any system downtime shall be formally communicated to the Client along with proper justification. Issues related to online services shall be rectified within 24 hours, and those requiring part replacement or physical service shall be resolved within 48 hours. Failure to restore the system within the specified timeframe shall entitle the Client to impose penalties on the Contractor.

1.5OEM warranty registration for all major equipment shall be completed by the Contractor, and documentary proof of the same shall be submitted.

1.6All works shall be carried out in accordance with the approved drawings, specifications, relevant IS codes, and the directions of the Engineer-in-Charge. The Contractor shall arrange and deploy all materials, manpower, tools, tackles, and machinery necessary for the satisfactory execution of the work.

1.7The Contractor shall provide complete documentation for the installed system, including as-built drawings, cable layouts, equipment locations, test reports, operation and maintenance manuals, and warranty certificates. All documents shall be submitted in both hard and soft copies to the Client prior to final handover.

1.8The Contractor shall also be responsible for providing operational training and basic maintenance instructions to the Client's re

presentatives after installation and commissioning. The system shall be formally handed over only after successful completion of training and acceptance by the Client.

1.9No activity shall be carried out without the presence of a responsible representative of the Contractor at site. The Contractor s

hall maintain proper housekeeping throughout the execution of works and shall clean and clear the site upon completion.

1.10All materials proposed to be used shall require prior approval of the Client/Engineer-in-Charge. Samples, along with detailed catalogues, shall be submitted for review before procurement. Only brand-new, high-quality materials conforming to relevant IS specifications shall be used, and all such materials shall be subject to approval.

1.11In addition to the equipment warranty, the Contractor shall provide a warranty for workmanship and installation quality for the one year from the date of completion. Any defects or deficiencies arising during this period shall be rectified by the Contractor at no additional cost to the Client.

1.12The Contractor will correct and replace any defects occurring within a period of one year from the date of possession of the flat. Any minor modifications and corrective works required by the customer of the builder within this period will be done by the Contractor, free of cost.

1.13Lifting, Shifting, Transport and Mathadi - The Contractor shall be solely responsible for the lifting, shifting, loading, unloading, and transportation of all construction materials, equipment, and machinery to and within the site during the execution of the works. This includes the movement of materials from ground level to the respective installation locations, as required. The Contractor shall also be fully responsible for handling, managing, and coordinating all Mathadi-related matters in accordance with applicable local laws and regulations. All costs related to lifting, shifting, transportation and Mathadi charges shall be deemed to be included in the quoted rates and no additional claims shall be entertained in this regard.

1.14Scaffolding - All necessary scaffolding, staging, and working platforms required for execution of the work shall be arranged and maintained by the Contractor at their own cost, ensuring safety and stability at all times.

1.15Housekeeping and Cleaning - The Contractor shall keep the work area clean, safe, and free from obstructions at all times. Surplus materials and equipment shall be stored or removed as directed by the Client. Upon completion of any work portion, the Contractor shall promptly clear the area of unused materials and equipment not needed for further work.

1.16Labour Camp Space, Power & Water - Labor camp shall be set up by the Contractor, as per the CREDAI rules and regulations, i.e. No bamboo and chatai. Electricity and water supply for labor camp shall be in contractor scope, arrangement for the same to be made by the Contractor, Contractor to employ one qualified Electrician for safety and proper wiring within the labor camp). No labor shall be allowed to live within the premises of the project.

1.17Water & Electricity - The Client shall provide water and electricity at a single point at the project site for use in cons truction activities. The Contractor shall make all necessary arrangements for distribution, storage, and usage from that point onward, at their own cost.

1.18Work Schedule - A detailed work and delivery schedule shall be submitted by the contractor prior to commencement and must be approved by the Engineer-in-Charge.

1.19Electricity shall be provided by the owner at one point only. Further distribution and wiring for the same is in contractor's scope. In case of activities after dark proper permission will be taken from the Site In charge, after displaying proper arrangement for the same. Permission of works at night will be totally at the discretion of the owner/PMC and the request for same may be refused.

1.20Safety - The Contractor shall ensure full compliance of Safety Code. All measures to ensure safety of workers and plant at site such as safety belts, safety helmets, safety goggles, safety gloves and safety shoes must be made mandatory for use on site, responsibility of which shall be taken by the Contractor. No Smoking & Spiting is allowed in the premises of

site. The contractor shall ensure full compliance of safety during using machinery with electrical wire. Electrical wire don't should not kept open. Non-compliance or non-conformance with EHS Requirements stated or implied shall be treated as offence. Contractor, its staff and workers will be penalized for each offence. Maintain proper documentation of safety protocols and adhere to all site-specific safety requirements.

1.21Quality - The Contractor shall ensure that all works are executed with the highest standards of quality and workmanship, adhering to good engineering practices and the instructions of the Engineer-in-Charge (EIC). All materials shall be new, of approved make, and conform to relevant Indian Standards (IS) codes and industry best practices. All work must conform strictly to the approved drawings, specifications, Good for Construction (GFC) details, technical guidelines, and any instructions issued by the Client or its Consultant. No deviations shall be permitted without prior written approval from the EIC.

1.22Compliances - The Contractor shall ensure full compliance with all applicable laws, regulations, and statutory requirements, including labor, safety, and environmental norms. The Contractor shall arrange necessary insurance for personnel and equipment at their own cost and submit copies of all licenses and permits before commencing work. Any non-compliance may result in penalties, legal action, or termination, and the Contractor shall indemnify the Client against all related liabilities.

1.23Testing & Certification - All tests specified in the tender documents or as required by the Electrical Consultant as per government norms and good engineering practices will have to be carried out by the electrical contractor, the cost for all the test is deemed to be included in tender amount.

1.24For material storage, if available client will provide a space for godown. All materials & labours required for material godown shall be in contractor's scope. Builder shall not be held responsible for any losses in terms of theft of otherwise. Contractor shall be responsible for the safekeeping of his own material.

1.25Defect Liability Period - The product offered shall be free from defects in design,, material and workmanship with a Defect Liability Period of 12 months commencing from the final handing over of electrical works.

1.26Maintenance and Serviceability - The free maintenance is for a period of 12 months and will commence from the date of handover. The rates & contract cost includes 12 (Twelve) months free maintenance service of the product - The free maintenance service will consist of regular & special examinations and any necessary actions required for smooth operation of the equipment. The Maintenance will be carried out by competent employees under the directions and supervision of the contractor. The Contractor shall attend to any maintenance complaint within 24 hours of notification.

1.27Payment stages - Payments will be made on a pro-rata basis, aligned with the progress of work completed on-site. Each payment will be processed upon certification and approval by the Site In-Charge.

Note: All payments by the client's accounting department will be released within 30 days of receiving the certified contractor's i

nvoice. Payments will be made through account payee Cheque or by money transfer to Contractor's Bank account.

1.28Completion Period - Time is the essence of this order and hence the execution schedule should be strictly adhered to. Contractor shall abide by the schedule integrated with general contractor agreed between client and contractor for execution of the work and shall throughout the term of the order co-operate with builder to avoid any delays in the completion.

1.29This is a Lump Sum Contract, under which the total contract value is fixed and all works are to be executed within the agreed price. Accordingly, no claims for additional quantities, rate variations, or extra charges shall be entertained or paid, even if higher quantities are encountered during execution due to site conditions or detailed measurements.

ARTICLE: 2 COMPENSATION FOR CONTRACTOR'S WORK

2.1 For all the works described in this order, a fixed and firm compensation of Rs. 2,06,500/- (Rs. Two Lakh Six Thousand Five Hundred Rupees Only) Including 18% GST

2.2 Payment stages will be as per the attached sheet (ANNEXURE II).

2.3 The above compensation will include any additional minor works that may be required as a necessity for the project.

2.4 All contractual prices, agreed and defined as compensation includes loading, unloading, transportation, and duties plus profit and covering all contractual obligations and risks as indicated in the Order are understood to be fixed and firm and not subject to escalation up to fulfilment of Contractual Obligations of both the Parties and shall not be subject to any adjustment due to any reason such as but not limited to any statutory variations.

2.5 The Builder, if applicable, will deduct any Tax, at source as per prevailing provisions of the law.

2.6 Retention of 5% of the total cost will be deducted from each RA bill which shall be released after completion of six (6) months from the date of final bill certification.

2.7 2 (two) copies of Contractor's invoices along with supporting documents duly certified by Site Engineer, clearly indicating the Order number shall be addressed to the Builder and submitted to the Builder Site office.

ARTICLE: 3 SAFETY & GENERAL RESPONSIBILITIES

3.1 Contractor's personnel deputed for the Work shall abide with all rules & regulations including the safety procedures prevailing at Site/ Office and shall be medically fit to perform the Work.

3.2 The Builder shall not be liable for any claim for loss or profits or any other consequential or direct / indirect damages that may be suffered by the Contractor during the execution of the work.

3.3 Contractor shall at all-time keep the Builder fully indemnified against any consequences arising out of Work Contractor's own or on account of Contractor's default or negligence.

3.4 While on duty, Contractor's personnel shall report to Builder's representative at Site and shall dutifully carry out the task assigned to them and follow the instructions.

3.5 The contractor shall take all safety measures on site such as safety helmets, safety belts, labor insurance etc. In case of any mishap on site only the contractor will be responsible for any consequences arising for such a situation. The contractor will not have any claim for the same.

3.6 No child labour will be permitted to work on site. If anyone is found, the Builder has the authority to stop the work immediately. During any governmental inspection if the same is identified, the contractor will be solely responsible for the consequences.

3.7 General and Statutory Obligations :

i. All statutory obligations, permits, licenses etc. in respect of the Work shall be done by the Contractor.

ii. Insurances for the Contractor's personnel and Equipment as applicable and in accordance with project requirements shall be arranged by the Contractor at his own cost and will submit a photocopy of all licenses and permits to the Builders office before starting work.

ARTICLE: 4 TERMINATION OF WORK ORDER

4.1 At the completion of works the Work Order shall be terminated in case of misbehavior, disobedience, dishonesty or negligence on the part of Contractor and/or his personnel or Contractor's failure to execute, complete and deliver the Work within the specified / reasonable time as decided by the Builder. Upon any such termination, the Builder shall pay in

accordance with the following:

All amounts due and not previously paid to Contractor for Work completed in accordance with the Order prior to any notice of termination, and for Work completed thereafter as specified in the notice, after deducting an amount as may be considered suitable to adjust for loss of work caused due to the Termination

The Builder has all rights, to recover from the Contractor, any loss that is incurred or foreseen due to the Contractor's default. The Builder shall not be held responsible for any damage, either direct and / or indirect, to the Work Contractor consequent on his exercising his right to early terminate or suspend the Order.

Certified and sanctioned by :

Agreed and Accepted :

M/s. Godiva Properties Private

M/s. VERTSCEND AUTOMATION PVT. LTD

Workorder No. : 2220005654

Workorder Amount : 2,06,500/- Including 18% GST

KOHINOOR WORLD TOWER - PHASE - II - PIMPRI BOQ - Time Laps CCTV			Vertscend Automation Pvt Ltd		
SN	Description	Unit	QTY	Rate	Total Amount
1.00	DS-7608NXI/I2/S - Time-lapse NVR - 08 CH Time-lapse NVR with 2 sata,80 Mbps bandwidth	Num	1.00	42,622.00	42,622.00
2.00	SS-NE30XSP-M5 - 6.0 MP Outdoor 30X IP Speed Dome Camera,Progressive Scan CMOS Sensor.POE Power Supply.Face. Detection and Vehicle Detection.	Num	1.00	42,620.00	42,620.00
3.00	8 TB HDD	Num	1.00	18,975.00	18,975.00
4.00	4 port poe with 2 giga uplink switch	Num	1.00	1,952.00	1,952.00
5.00	5x5 PVC Box for camera connection	Num	2.00	85.00	170.00
6.00	4 U Wall Mount Rack with tray & PDU and accessories	Num	1.00	2,660.00	2,660.00
7.00	19" HDMI&VGA monitor	Num	1.00	3,832.00	3,832.00
8.00	Installation, integration, testing and commissioning of the system	Num	1.00	28,500.00	28,500.00
9.00	Suplying & Layingof CAT6 cable with all needfull accessories like PVC condute, Sockets, Saddel etc.Approx per MTRs Charges	Mtr	150.00	85.00	12,750.00
10.00	Suplying & Layingof 6 Core Fyber Unarmoured cable with all needfull accessories like PVC condute,Sockets, Saddel etc.Approx per MTRs Charges	Mtr	200.00	72.00	14,400.00
11.00	Fyber Media Convertor	Num	1.00	2,959.00	2,959.00
12.00	2 Way Big Enclosure	Num	2.00	140.00	280.00
13.00	Pigtel	Num	4.00	70.00	280.00
14.00	Splicing	Num	4.00	550.00	2,200.00
15.00	Outdoor Network Box	Num	1.00	800.00	800.00
				Net Total Amount	1,75,000.00
				GST (9% + 9%)	31,500.00
				Total Taxable Amount	2,06,500.00